

**2021 STREET PROGRAM, HOMESTEAD DRIVE, ABBOTSBURY PLACE & WILLOWBROOK LANE
EDGEWOOD, KY
PROJECT NO. 21044**

**BRANDSTETTER CARROLL INC.
ARCHITECTS ENGINEERS PLANNERS**

May 7, 2021

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

1. The attached revised Bid Form shall be used to submit the bid. Please note the following changes to the Bid Form, Clarifications to the Supplemental Specifications and new detail.
 - A. Clarifications:
 1. Pay Item 2, This is intended to reconstruct a portion of a driveway so as to meet the grade of the new curb. This work shall be completed As Directed by the Engineer.
 2. Pay Item 6, On average the depth of the milling shall be 2.5". The depth of the milling may be adjusted on the field depending on the conditions encountered.
 3. Pay Item 7, The new curb shall meet the existing drives similar to the existing top of curb profile per the existing curb. Note that 100% of the curb on this street shall be removed and replaced.
 4. Pay Item 8, The existing Catch Basins shall be adjusted to grade As Directed by the Engineer.
 5. Pay Item 9, The new stop bar pavement marking shall be with thermoplastic paint.
 6. Pay Item 11, The full depth asphalt pavement repair shall be 6" deep (Not 8" deep as indicated on the detail on page 57).
 7. Pay Item 12, The average depth of the partial depth pavement repair shall be 4".
 8. Pay Item 18, The concrete curb and gutter remove and replace shall be a minimum of 3' in length.
 9. Pay Item A1-4, Shall include the woven geotextile fabric as indicated on page 54.
 10. Pay Item A1-5, 6" Underdrain shall be located immediately behind the curb.
 11. Pay Item A1-6 shall include the removal of existing bad subgrade soil and replaced with KTC Section 302 Crushed Stone Base. The estimated quantity is 25 CY. As Directed.
 12. Pay Item 14, The leveling shall be 1.5" thick. The estimated quantity is 60 Ton.

13. Pay Item 15, The estimated quantity is 60 Ton.
14. Pay Item 20, The estimated quantity is 30 Ton.
15. Pay Item 22, The estimated quantity is 175 Ton.
16. Pay Item 23, The estimated quantity is 175 Ton.
17. Pay Item 25, The average depth of the Pavement Milling shall be 2.5".
18. Pay Item 26 shall not apply.
19. Pay Item 27 shall include the removal and disposal of existing asphalt curb.
20. Pay Item 28, the new stop bar pavement marking shall be with thermoplastic paint.
21. Pay Item 31 shall read: "Concrete Road Pavement Remove and Replace".
22. Pay Item 32, The unit of measurement shall be SY (Square Yards).
23. Pay Item 33, Shall be spec. Item Special. Inlet reconstruction at 615 Willowbrook Lane. It shall be as follows: The existing storm inlet shall be reconstructed to 12" higher than the existing inlet. The purpose of the window is to provide drainage from the adjacent yard. The scope of this pay item shall include the grading, topsoil and turf restoration.

Also included is the removal and reconstruction of the 4" thick concrete channel, approximately 24 S.F.

The new concrete channel shall generally match the dimensions of the existing channel.
24. All tack coat shall be tackless.
25. Please see the attached detail for the standard Concrete Curb, Pay Item 27.
26. On Homestead Drive the underdrain shall be located beneath the new curb.

Attachments: Revised Bid Form
Special Item Inlet Reconstruction at 615 Willowbrook Lane.
Extruded Concrete Curb Detail

End of Addendum No. 2

BID FORM

Project: **2021 STREET PROGRAM - HOMESTEAD** Bidder:
DRIVE, ABBOTSBURY PLACE &
WILLOWBROOK LANE
EDGEWOOD, KY
21044

In compliance with your **Invitation for Bids**, the undersigned Bidder(s) hereby proposes to furnish all materials and perform all the work necessary for the construction of the above referenced project, in strict accordance with the Contract Documents as prepared by Brandstetter Carroll Inc., and within the time set forth within and at the price stated in this form.

By submission of this BID, each BIDDER certifies, and in the case of a joint BID, each party thereto certifies as to his own organization, that this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

BIDDER hereby agrees to commence work under this contract on or before a date to be specified in the **NOTICE TO PROCEED** and to fully complete the PROJECT within calendar days thereafter. BIDDER further agrees to pay as liquidated damages, the sum of **\$1,000.00** for each consecutive calendar day thereafter as provided in the General Conditions.

Bidder acknowledges receipt of the following ADDENDUM:

**BID FORM
2021 STREET PROGRAM
HOMESTEAD DRIVE
21044**

| PAY | | | | | | |
|---|-------------|---|------------|-------------|-------------|--------------|
| ITEM | SPEC | DESCRIPTION | QTY | UNIT | COST | TOTAL |
| 1 | 112 | Maintain Traffic | 1 | LS | | |
| 2 | 302 | 7" Concrete Drive Remove and Replace as Directed (7") | 550 | SF | | |
| 3 | 407 | Trackless Tack Coat | 320 | Gal | | |
| 4 | 403 | Leveling Course (1.5") | 260 | Ton | | |
| 5 | 403 | Surface Course (1.5") | 260 | Ton | | |
| 6 | 408 | Pavement Milling | 3,110 | SY | | |
| 7 | 506 | Concrete Curb and Gutter Remove and Replace (30") | 2,400 | LF | | |
| 8 | 638 | Adjust Catch Basin to Grade as Directed | 3 | EA | | |
| 9 | 644 | Stop Bar (Thermoplastic) | 10 | LF | | |
| 10 | 704 | 6" Underdrain | 2,400 | LF | | |
| 11 | SPEC | Full Depth Asphalt Pavement Repair | 50 | Ton | | |
| 12 | SPEC | Partial Depth Pavement Repair | 65 | Ton | | |
| SUB-TOTAL BASE BID ITEMS 1 THRU 12 | | | | | | |

ALTERNATE NO.1 -FULL DEPTH REPAIR CONCRETE PAVEMENT

| | | | | | | |
|---|---------|---|-------|----|--|--|
| A1-1 | 112 | Maintain Traffic | 1 | LS | | |
| A1-2 | 203 | Pavement Removal | 3,110 | SY | | |
| A1-3 | 207 | Subgrade Reshaping and Compacting | 3,110 | SY | | |
| A1-4 | 302/501 | Concrete Pavement (7" Concrete/6" Aggregate Base with Integral Rolled Curb) | 3,110 | SY | | |
| A1-5 | 704 | 6" Underdrain | 2,400 | LF | | |
| CONTINGENCY ITEMS | | | | | | |
| A1-6 | SPEC | Subgrade Repair as Directed | 25 | CY | | |
| TOTAL ALTERNATE ITEMS A1-1 THRU A1-6 | | | | | | |

BID FORM**ABBOTSBURY PLACE****EDGEWOOD, KY****21041**

| PAY ITEM | SPEC | DESCRIPTION | QTY | UNIT | COST | TOTAL |
|--|-------------|---|------------|-------------|-------------|--------------|
| 13 | 112 | Maintain Traffic | 1 | LS | | |
| 14 | 403 | Leveling Course (1.5") | 60 | Ton | | |
| 15 | 403 | Surface Course (1.5") | 60 | Ton | | |
| 16 | 407 | Trackless Tack Coat | 65 | Gal | | |
| 17 | 408 | 2" Milling | 650 | SY | | |
| 18 | 506 | Concrete Curb and Gutter Remove and Replace | 200 | LF | | |
| 19 | 638 | Adjust Valve Box to Grade | 1 | LS | | |
| 20 | SPEC | Full Depth Asphalt Pavement Repair | 30 | Ton | | |
| SUB-TOTAL BASE BID ITEMS 13 THRU 20 | | | | | | |

BID FORM**WILLOWBROOK LANE****EDGEWOOD, KY****21041**

| PAY ITEM | SPEC | DESCRIPTION | QTY | UNIT | COST | TOTAL |
|---|-------------|--|------------|-------------|-------------|--------------|
| 21 | 112 | Maintain Traffic | 1 | LS | | |
| 22 | 403 | Leveling Course (1.5") | 175 | Ton | | |
| 23 | 403 | Surface Course (1.5") | 175 | Ton | | |
| 24 | 407 | Trackless Tack Coat | 210 | Gal | | |
| 25 | 408 | Pavement Milling (avg. 2.5") | 2,100 | SY | | |
| 26 | - | No Used | - | - | - | - |
| 27 | 609 | Extruded Concrete Curb Remove and Replace | 200 | LF | | |
| 28 | 644 | Stop Bar (Thermoplastic) | 12 | LF | | |
| 29 | SPEC | Full Depth Asphalt Pavement Repair | 30 | Ton | | |
| 30 | SPEC | Partial Depth Repair | 20 | Ton | | |
| 31 | SPEC | Concrete Road Pavement Remove and Replace (10") in Cul-de-sac, Two Half Blocks | 120 | SY | | |
| 32 | SPEC | Asphalt Driveway Remove and Replace (4") | 120 | SY | | |
| 33 | SPEC | Inlet Reconstruction at 615 Willowbrook Lane. | 1 | LS | | |
| SUB-TOTAL BID ITEMS 21 THRU 33 | | | | | | |
| GRAND TOTAL BASE BID ITEMS 1 THRU 33 | | | | | | |

BID SUMMARY

Total Bid Items 1 thru 33 in Figures: \$ _____

Total Bid Items 1 thru 33 in Words: _____

Total Alternates A1 -1 thru A1-6 in figures: \$ _____

Total Alternates A1-1 thru A1-6 in words: _____

Amount of Bid to be shown in both figures and words. In case of discrepancy, the amount tabulated from the unit prices shall govern.

Respectfully Submitted:

Signature: _____

Street Address: _____

Title: _____

City/ST/Zip: _____

Company: _____


Date: _____

Telephone: _____

Email: _____

Item Special- Inlet Reconstruction at 615 Willowbrook Lane

It shall be as follows: The existing storm inlet shall be reconstructed to 12" higher than the existing inlet. The purpose of the window is to provide drainage from the adjacent yard. The scope of this pay item shall include the grading, topsoil, and turf restoration.



CONCRETE EXTRUDED CURB
NOT TO SCALE